BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of Work: Detailed Estimate for the work of Maintenance of BBMP office building in ward No-02 of Yelahanka Sub Division. | **Estimate Cost Rs.** | **300000.00**

Sl No	Description Of Work	Qty		Rate	Unit	Amount
	PART-A					
4 50/34	Supplying and fixing/replacing of 6/16/32 Amps electrical accessories on existing switch board. Group A					
	h) 6 Amps Bell Buzzer	10		110.00	Each	1100.00
	a) 6Amps SP Switch	10		31.00	Each	310.00
	c) 6Amps 3Way 5 Pin Socket	10		41.00	Each	410.00
	j) 16 Amps 3 way 5 pin socket	10		84.00	Each	840.00
	k) 16 Amps 3 pin Top	10		72.00	Each	720.00
	l) 32 Amps Bakelite DP	10		132.00	Each	1320.00
5 54/52	Supply and fixing of 230 volts 20/40 watts starter for fluorescent lamp. a) Group A	200		18.00	Each	3600.00
6 53/48	Supplying and fixing/replacing of flouresexcnt tube. a) 18 to 40 watts	200		65.00	Each	13000.00
7 46/19	Supplying of 65/80 watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes.	98		480.00	Each	47040.00
8 47/21	Supply of Specital type lamps h) 36 Watts CFL	40		190.00	Each	7600.00
11 51/36	Rewinding a...mm ceiling fan/after using necessary gauge annealed and insulated copper wire with necessary insulating, separators vibration arresting shellac, etc including replacement of bearings if any transportation to and from the spot to workshop inclusive of releasing the refixing. c) 1200MM	20		630.00	Each	12600.00
12 51/37	Releasing the existing fan dismantling testing painting after removing the existing painting by scraping and cleaning (Spray method) to less than 2 coats of approved make enamel paint to a ceiling fan and wiring and fixing of the same.	20		245.00	Each	4900.00

13 52/44	Releasing the existing FTL Fitting all capacities, checking, testing and installing at same place.	60		30.00	Each	1800.00
15 54/62	Supplying and fixing Cordless calling bell suitable to operate on 230V 50 Hz AC/3V DC Supply, Cordless remote bell push with 2x1.5V DC Batteris and completely wired. a) Group A	4		650.00	Each	2600.00
	PART-B					0.00
5 84/9	Supplying & fixing relay for over load protection for window and split air conditioners.	4		260.00	Each	1040.00
3 83/7	Supply and fixing of condensing coil for Split Air Conditioners. c) 2 ton capacity	4		4750.00	Each	19000.00
4 84/8	Supplying and fixing capacitor's (of approved make) for window/ split air conditioners b) 80 to 200 mfd Starting capacitor	4		300.00	Each	1200.00
7 84/11	Supplying & filling refrigerent (F-22/F/12) for air conditioning equipments. Which includes the labour & Nitrogen gas for pressure and leak testing.	6		810.00	P/Kg	4860.00
8 84/13	Supplying and fixing electro mechanical/Pneumatic time switches including Vat.	4		960.00	Each	3840.00
	Lowest Quotation Rates					0.00
	PART- C					0.00
17	Repairs to Motors: Rewinding of submersible pumpsets with copper insulation wire of suitable guage as per ISI specification with guarantee of 6 months above 5HP up to 10HP	1		2000.00	Each	2000.00
18	Impeller (Shell moulded with Aluminium & Branze)	1		220.00	Each	220.00
19	Replacement of Motors Parts; Above 4HP below 5HP Rotor	1		2400.00	Each	2400.00
20	Re-Errection Charges of pumping Machineries including overhauling and painting	1		400.00	Each	400.00
21	Lifting of submersible pumpset	1		400.00	Each	400.00
22	Labour charges (overhauling)	1		400.00	Each	400.00
23	Discharge out let (DO) Bearing DO Steel bush	1		400.00	Each	400.00
24	Guide Vane	1		200.00	Each	200.00
25	Pump shaft made out of Stainless steel centreless ground with key way (up to 8 stage)	1		330.00	Each	330.00

26	Non- Retune valve (NRV) assembly complete with rubber 'O' Ring	1		365.00	Each	365.00
27	Carbon housing	1		345.00	Each	345.00
28	Thrust bearing block assembly complete with segment bearing pad	1		519.00	Each	519.00
29	Tip Carbon/Ferrodo Padding	1		230.00	Each	230.00
	PART-D					
	Removing, Testing, Charging & Re-Errecting of Batteries of 100 to 180 Amps. Every three months	70		250.00		17500.00
	Annual Maintenance of ups unit of 1-8 KVA including of replacement of Parts etc.	4		8000.00		32000.00
	Maintenance of Diesel Generator Set				L/s	15000.00
30	Supplying of PROJECTOR with SCREEN and Television(LED)				L/s	99000.00
	Miscellenous					511.00
	TOTAL					**300000.00**

(Rupees Three Lakhs Only)

CERTIFICATE-

1. The place was inspected and the work is essential.
2. The provision made in the estimate are adequate and necessary And the work comes in the corporation limit and is legitimate Charges on the corporation funds.
3. The estimate is based on PWD (Ele) S. R 2010-11Rates Lowest Quotation Rates .

Ramesh

Assistant Engineer

Asst. Executive Engineer
Yelahanka Sub Division
BBMP, Bangalore-64.

Executive Engineer
Yelahanka Division
Bangalore-64

Administrative Sanction for Rs 3.00 Lakh
Three Lakhs
2014
is accorded under head P. 1771
2014-15
Registered as CE No. ..... Subject
to ... ns contained in enclosed memo
No. EE/YNK/AA/33/14-15 Dt 27-10-14

Executive Engineer

TECHNICALLY SANCTIONED FOR Rs. 3.00 Lakh
Rupees Three Lakh only
Under P. 1771 - 2014-15
Registered as CE ( ) No .....
Subject to conditions contained in
enclosed memo ES ( ) No ..... /
Dt ..... Estimate / Sanctioned
EE/YNK/TS/59/14-15 No.
Dated 28-10-14 Rs. 3.00 Lakh

Executive Engineer